
## Precast Concrete 3'-0" X 5'-0" X 4'-0" Communication Splice Box



## STANDARD SPLICE BOX FEATURES

- Designed for HS-20 Loading
- Thin Wall Knockouts for Easy Cable Splicing (shown)
- Pull Irons Cast In Floor (shown)
- Ø6" Recessed Sump in Floor (shown)
- Ø2" Ground Rod Hole in Floor (shown)
- Hot Dipped Galvanized Steel Cover (shown)
- Diamond Plate Finish on Cover (shown)
- Smooth Corners for Safe Installation & Quality &...It Just Looks Better!

## SPLICE BOX OPTIONS

- Unistrut Cast Into Wall for Racking in lieu of Bolt Inserts
- Terminators Cast Into Wall in lieu of Thin Wall Recess
- Non-Metallic Racking
- Plastic Coated Racking
- Cast In Grounding Lug
- Pull Irons Add or Change Locations
- Black Painted in lieu of Hot Dipped Galvanized
- Aluminum LId in lieu of Hot Dipped Galvanized
- Divider Plate for Multi-Purpose Boxes



PROUDLY BASED IN HOUSTON, TEXAS T:832-804-7062 F:832-804-7071 E:info@lockesolutions.com

## LOCKESOLUTIONS.COM